

98 SEP -8 PM 2:05

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Charles M. Cook
 REGISTER OF DEEDS

For corners in

Charlevoix

(County)

Located In:

Corner Code #

1. Public Land Survey

T 32N R 7W G-13

T 31N R 7W G-1 ANTRIM

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. , Recorded Plat
 5. Private Claims

SURVEY &
 REMONUMENTATION

OCT 19 1998

SECTION

Register of Deeds Stamp & File Number

Wayne E. Boss

June 98

I, Wayne E. Boss, in a field survey on June, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-13 OCTOBER, 1856 BEFORE NOVEMBER 1892
 EDWARD D. ATWATER, DEPUTY SURVEYOR E.K. ROBINSON, COUNTY SURVEYOR
 SET SECTION CORNER FOUND POST
 SUGAR 12 INCH N41 3/4°E 50 LINKS SUGAR 12" N41 3/4°E 53 LINKS
 BEECH 12 INCH N16°W 77 LINKS BEECH 12 INCH N16°W 77 LINKS
 OLD CORNER 21.71 LKS. N & 5.73 LKS. WEST JUNE 1, 1978 LAWRENCE R. FEINDT, P.S.
 MARCH 4, 1974, WAYNE E. BOSS, P.S. FD. 1" PIPE FD. 1" PIPE, POLE N35°E 61.55', 8" FRUIT TREE N70°E 55.59'
 ELECTRIC POLE N35°E 61.88 NAIL W. FACE 12" MAPLE S15°W 104.88'
 8" FRUIT TREE N70°E 55.59' NAIL E. FACE 12" MAPLE S15°W 104.88' PK NAIL E. FACE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13
 APRIL 23, 1998
 FOUND 1" PIPE 6" BELOW SURFACE OF WATERMAN ROAD CENTER LINE
 FD. OLD SHAFT 16" BELOW SURFACE
 ELECTRIC POLE N35°E 61.88 NAIL GONE
 10" FRUIT TREE N70°E 55.59' NAIL COVERED OVER AND SURROUNDED WITH THORN TREES
 16" MAPLE S15°W 104.88' NAIL GROWN OVER
 H-13 TO G-13 GLO 40 CHAINS (2640.0') E.K. ROBINSON 39.72 CHAINS (2621.52') MEASURES 2600.46'
 G-13 TO F-13 GLO 40 CHAINS (2640.0') MEASURES 2628.00'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13
 PLACED STEEL CHARLEVOIX COUNTY MARKER
 ELECTRIC POLE N42°E 62.12' SET NAIL & TAG
 8" APPLE N64°E 109.17' SET NAIL & TAG
 8" RED PINE S72°E 51.39' SET NAIL & TAG
 16" MAPLE S19°W 104.96' SET NAIL & TAG

Charlevoix Co. Surveyor
APPROVED
 Signature Mary C. Feindt
 Date: Aug 13 1998

AND IS ACCEPTED AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Wayne E. Boss*
 Surveyor's Michigan License No. 20703

Date Aug 13 1998
 STATE OF MICHIGAN
 WAYNE E. BOSS
 PROFESSIONAL SURVEYOR
 No. 20703