

**SURVEY & REMONUMENTATION**

OCT 19 1998

**SECTION**

For corners in

Charlevoix

(County)

Located in:

Corner Code #

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

32N	R	7W	I-13
T	R		
71N	R	7W	I-1 ANTRIM
T	R		
S	T	R	
S	T	R	
S	T	R	
S	T	R	

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF CHARLEVOIX  
RECEIVED FILE RECORD

98 SEP -8 PM 2:10

*Charlotte M. Robison*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Wayne E. Boss

JUNE 98

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-13 OCTOBER 1856 EDWARD D. ATWATER, DEPUTY SURVEYOR SET SECTION CORNER SUGAR 14 INCH N37 1/2\*E 36 LINKS SUGAR 16 INCH N21 1/2\*W 13 LINKS OLD FOUND 19.80 LINKS NORTH & 3.87 LINKS WEST JUNE 19, 1978, LAWRENCE R. FEINDT, P.S. FOUND CORNER, NO WITNESSES NOTED

BEFORE NOV. 18, 1892 E.K. ROBINSON FOUND POST 39.75 CHAINS EAST OF S 1/4 POST SUGAR 14" N37 1/2\*E 36 LINKS SUGAR 16" N21 1/2\*W 13 LINKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13 FEB. 20, 1998 FOUND 3/4" PIPE BY FENCE ANCHOR POST 10" BASSWOOD N90\*E 23.35' TAG 31601 14" MAPLE S02\*E 10.05' TAG 31601 TWIN 16" MAPLE S62\*W 24.21' TAG 31601 5" IRONWOOD NORTH 10.08' TAG 31601 FOUND OTHER ANCHOR POST N09\*W 23.2' J-13 TO I-13 GLO 40 CHAINS (2640.0') MEASURES 2636.11' I-13 TO H-13 GLO 40 CHAINS (2640.0') MEASURES 2599.35'

Charlevoix Co. Surveyor  
**APPROVED**  
Signature *Wayne E. Boss*  
Date: *Aug 13, 1998*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 APRIL 23, 1998 PLACED STEEL CHARLEVOIX COUNTY MARKER 10" BASSWOOD N90\*E 24.05' SET NAIL & TAG 14" MAPLE S02\*E 10.80' SET NAIL & TAG TWIN 16" MAPLE S62\*W 25.54' SET NAIL & TAG 5" IRONWOOD NORTH 10.44' SET NAIL & TAG



AND IS ACCEPTED AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

Signed by

*Wayne E. Boss*  
20703

Date

*Aug. 24, 1998*

LIBER 003 PAGE 179