

SURVEY & REMONUMENTATION

OCT 19 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECORDED FOR RECORD

98 SEP -8 PM 2:11

Charlene M. Bales
REGISTER OF DEEDS

For corners in

Charlevoix

(County)

Located In:

Corner Code #

1. Public Land Survey

T 32N R 7W

J-13

T R

T 31N R 7W

J-1

ANTRIM

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Wayne E. Boss

June

98

I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-13 OCT. 1856 ED. D. ATWATER, DEPUTY SURVEYOR SET CORNER
(1 IRONWOOD 6 INCH N45*W 7 LINKS
(2 SUGAR 5 INCH S54 1/2*E 19 LINKS

MAY 28, 1988, BERYL M. JONES, P.S.
FOUND 3/4" PIPE
(3 R.O.W. MARKER EAST 19.90'
(4 1/2" IRON S55*E 54.60'
(5 WEST R.O.W. MARKER 62.03'
(6 1/2" IRON S60*W 113.02'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13 FEB. 20, 1998
FOUND 3/4" PIPE IN MONUMENT BOX IN GRAVEL SHOULDER OF HIGHWAY M-66
EAST EDGE OF ASPHALT WEST 2.0'
(3 R.O.W. MARKER EAST 19.18'
(7 R.O.W. MARKER EAST 57.70'
K-13 TO J-13 GLO 40 CHAINS (2640.0') MEASURES N89*15*06"W 2625.75'
J-13 TO I-13 GLO 40 CHAINS (2640.0') MEASURES N89*387*35"W 2636.11'

Charlevoix Co. Surveyor
APPROVED

Signature *Mary C. Feendt*
Date: *Aug 13, 1998*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 3/4" PIPE IN MONUMENT BOX IN GRAVEL SHOULDER OF HIGHWAY M-66
EAST EDGE OF ASPHALT WEST 2.0'
(3 R.O.W. MARKER EAST 19.18;
(7 R.O.W. MARKER EAST 57.70'
(8 FENCE POST WEST 92.57', NEXT TO BROKEN RIGHT OF WAY MONUMENT
(9 WESTERLY POST OF NO PASSING ZONE SIGN S12*E 73.89'
(10 ANTRIM COUNTY SIGN N28*W 114.77'



AND IS ACCEPTED AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Wayne E. Boss*

Date *Aug. 24, 1998*

Surveyor's Michigan License No. 20703

LIBER 003 PAGE 180