

SURVEY & REMONUMENTATION

OCT 19 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970.

For corners in

Charlevoix

(County)

Located In:

Corner Code #

1. Public Land Survey

32N R 7W K-13
T R
31N R 7W K-1 ANTRIM
T R

2. Property Controlling in Section

S T R
S T R

3. Miscellaneous Property in Sec.

S T R
S T R

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED

98 SEP -8 PM 2:12

Charlene M. Chabon
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Wayne E. Boss

July 98

I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

<p>K-13 OCTOBER 1856 EDWARD D. ATWATER, DEPUTY SURVEYOR SET SECTION CORNER ELM 12 INCH N64 1/2*E 14 LINKS SUGAR 8 INCH N23 1/2*W 32 LINKS</p>	<p>OCTOBER 13, 1960 G. SHADKO, PLACED MICHIGAN DEPARTMENT OF CONSERVATION CONCRETE MONUMENT, USING RETRACEMENT OF ROBINSON NOTES, NO WITNESSES NOTED DECEMBER 1966, MARY C. FEINDT FD. CONCRETE MONUMENT, NO WITNESSES NOTED</p>
---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 NO EVIDENCE OF OLD CORNER FOUND OR OLD WITNESSES.
GLO DISTANCE FROM EAST SIDE OF PINE RIVER (NOW JORDAN RIVER) TO OLD CORNER 7.67 CHAINS (506.22') RIVER LISTED AS 100 LINKS WIDE OR 66'
JULY 31, 1998 FOUND MICHIGAN DEPARTMENT OF CONSERVATION CONCRETE MONUMENT WITH BRASS TOP PLATE IN PLACE, 1.49' SOUTH OF OLD EAST WEST FENCE
K-13 TO J-13 GLO 40 CHAINS (2640.0') MEASURES N89*15'06"W 2625.75'
K-13 TO L-13 GLO 40 CHAINS (2640.0') MEASURES S89*20'08"E 2615.89'

Charlevoix Co. Surveyor
APPROVED
Signature Mary C. Feindt
Date: Aug. 13, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 MICHIGAN DEPARTMENT OF CONSERVATION MONUMENT AS FOUND
14" CHARED EVERGREEN STUMP N60*W 12.5'
4" POPLAR S50*E 9.92' SET NAIL & TAG
5" POPLAR N8*E 15.59' SET NAIL & TAG
8" POPLAR N37*W 23.57' SET NAIL & TAG
5" POPLAR S85*W 36.70' SET NAIL & TAG
WEST BANK OF JORDAN RIVER EAST 359.5'



AND IS ACCEPTED AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

Signed by Wayne E. Boss
Surveyor's Michigan License No. 20703

Date Aug. 24, 1998