

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Charles M. ...
 REGISTER OF DEEDS

For corners in
 Charlevoix
 (County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>32N</u> R <u>7W</u>	<u>M-3</u>
	T <u>32N</u> R <u>6W</u>	<u>A-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Wayne E. Boss, in a field survey on OCTOBER 23, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | |
|-----|--|--|--|
| M-3 | GLO SEPT 1856
E.D. ATWATER
SET COR. OF SEC. 1 & 12
1. BEECH 15 N84 1/2 W 8 LKS.
2. BEECH 9 S24W 35 LKS.

E.K. ROBINSON RE-WIT COR.
IN 1880'S (BK. 8)
3. BEECH 10 N 31 1/2 E 79 | 4. BEECH 11 S 84 1/4 E 39
ALSO USED IN MAY & JUNE
1886 SURVEY (BK 40 & 43)

E.A. ROBINSON APR. 1913
FD. OLD COR. SET NEW
3" STAKE (PILED STONES
IN HOLE 3 FT. SQUARE)
5. SUGAR 9. S32 1/2 E 139 1/2 LKS. | 1/4" PIPE SET BY UNKNOWN. USED
L. FEINDT & J. FERGUSON IN SUB-
SEQUENT SURVEYS.
6. 5" MAPLE SOUTH 13.28'
7. 5" MAPLE N40E 15.30'
8. 3" MAPLE S80E 7.60' |
|-----|--|--|--|

SURVEY
 REMONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-3 FOUND 1/4" PIPE
 6. 8" MAPLE SOUTH 13.48' SPIKE FOUND
 7. 5" MAPLE N40E 15.35' SPIKE FOUND
 8. 3" MAPLE S80E 7.64' SPIKE RESET
 9. 8" MAPLE NORTH 18.24' SPIKE FOUND
 10. 16" POPLAR N70W 13.44' SPIKE FOUND
 11. 16" POPLAR S20E 14.57' SPIKE FOUND
 12. FENCE COR. W/FENCE LINE REMENTS SOUTH & EAST

NOV 21 1997

COMMISSION

Charlevoix Co. Surveyor
APPROVED
 Signature Mary C. Feindt
 Date: Nov 9, 1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-3 & A-3 M-3 T32N-R7W COMMON CORNER TO A-3 T32N-R6W
 6. 8" MAPLE SOUTH 13.48' SPIKE FOUND
 7. 5" MAPLE N40E 15.35' SPIKE FOUND
 8. 3" MAPLE S80E 7.64' SPIKE RESET
 9. 8" MAPLE NORTH 18.24' SPIKE FOUND
 10. 16" POPLAR N70W 13.44' SPIKE FOUND
 11. 16" POPLAR S20E 14.57' SPIKE FOUND
 12. FENCE COR. W/FENCE LINE REMENTS SOUTH & EAST
 AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



Signed by *Wayne E. Boss* Date 11/29/96

Surveyor's Michigan License No. 20703