

REVISED

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORDS

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

99 SEP 16 PM 2:22

Caroline M. Nanting

REGISTER OF DEEDS

RECORDED
FEB 01 2000

FEB 01 2000

SECTION
Register of Deeds Stamp & File Number

For corners in

Charlevoix
(County)

Located in:

Corner Code #

-001

- 1. Public Land Survey T 32N R 7W MC WEST I-1
T 33N R 7W _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
In Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Wayne E. Boss, in a field survey on JULY, 19 99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M.C. BETWEEN I-1 & H-1
GLO JUNE 1839
JOHN HODGSON
EAST MARGIN OF A LAKE
A CEDAR 14 IN DIAMETER
FOR MEANDER POST

NO OTHER CORNER
RECORD OR CORNER
LOCATION FOUND.

Charlevoix Co. Surveyor
APPROVED
Signature Mary C. Ferrell
Date: Aug 19, 1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M.C. NO EVIDENCE FOUND. CORNER LOCATION ESTABLISHED AT GLO DISTANCE OF 1617 FT. BY PROJECTING THE NORTH LINE OF SECTION 2 WEST TO THE LAKE. DISTANCE FELL ON TOP OF BANK WHICH IS WHERE THE MEADNER CORNER MOST PROBABLY WOULD HAVE BEEN SET. JULY 1999, CORNER WAS ADJUSTED TO NORTH TO FIT SECTION LINE EVIDENCE AS SHOWN ON A SURVEY BY FERGUSON & CHAMBERLAIN ASSOCIATES DATED JANUARY 12, 1998.

- 1. S.E. COR. MAIN HOUSE ALTERED
- 2. 12" CEDAR N20*W 36.16' IS GONE
- 3. 10" CEDAR N75*E 7.65' FOUND
- 4. TWIN 5" CEDAR S20*E 19.76' FOUND
- 5. C/L DRIVE NORTH 22' DRIVE STILL USED
- 6. WEST OT WATER'S EDGE STILL CHECKS 153'+/-

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M.C. BETWEEN I-1 & H-1 T32N-R7W COMMON TO M.C. BETWEEN I-13 AND H-13 T32N-R7W
CHARLEVOIX CO. MON. RESET
1. S.E. COR. OF NEW ADDITION TO HOUSE N60W 44.34"
3. 10" CEDAR S17E 19.78' ADJUSTED NAIL & TAG
5. C/L DRIVE NORTH 6'
6. WEST TO WATER'S EDGE 153'
7. 12" CEDAR S82W 32.33' SET NAIL & TAG



Signed by *Wayne E. Boss*
Surveyor's Michigan License No. 20703

Date 8/19/99