

SURVEY & REMONUMENTATION

JAN 26 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF CHARLEVOIX
 RECEIVED FOR RECORD

97 DEC 16 AM 10:23

Charlene M. Crocker
 REGISTER OF DEEDS

For corners in

<u>CHARLEVOIX</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>32NR 6W</u>	<u>C-1</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, ARTHUR R. RANGER, in a field survey on SEPT. 15, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-1 corner common to Sec.'s 5 & 6, T.32N., R.6W.
 1856-E. D. Atwater set a closing corner 843 lks West of the corner common to Sec.'s 31 & 32 of T.33N., R.6W. And witnessed: Sugar 13" S27.5°E 16lks; beech 10" S75°W 51 lks.
 1877-E.K. Robinson worked along the Town line in Sec. 31, T.33N., R.6W.
 1887-E.K. Robinson found the Gov't corner and used in his survey in Sec. 5, T.32N., R.6W.—witnesses same as above.
 1973-Charlevoix Abstract sketch of Town line—no corner was found at that time.
 1974-Mary Feindt set a t-iron based on Robinson proration.
 1980-Danny Bongiovanni found a t-iron and used in his survey in Sec. 5, T.32N., R.6W., and witnessed: 6" Bass. N60°E 140.26'; T-iron West 417.70'; T-iron West 659.71'
 1980-Danny Bongiovanni found t-iron and recorded in a L.C.R.C. (L.002, Pg. 106) same witnesses as above.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1 corner common to Sec.'s 5 & 6, T.32N., R.6W.
 1997-Arthur R. Ranger, found the Feindt t-iron and witnesses of record; The corner fits Robinson measurements to East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1 corner common to Sec.'s 5 & 6, T.32N., R.6W.
 (Set a Charlevoix County Marker)
 12" Basswood clump N09°E 261.25'
 6" Elm N39°E 165.29'
 12" Basswood N68°E 139.70'
 t-iron East 141.40'
 t-iron West 417.70'

Charlevoix Co. Surveyor:
APPROVED
 Signature Mary C. Feindt
 Date: 12-11-97

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Arthur R. Ranger

Date 12/09/97

Surveyor's Michigan License No. 31601



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1996