

**SURVEY &
REMONUMENTATION**

JAN 26 1998

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED DEEDS RECORD

97 DEC 16 AM 10:22

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Charlotte D. Coakley
REGISTER OF DEEDS

For corners in

<u>CHARLEVOIX</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>32NR 6W</u>	<u>D-1</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1				●									
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

I, ARTHUR R. RANGER, in a field survey on SEPT. 15, 1997
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
D-1 North 1/4 corner Sec. 5, T.32N., R.6W.
(Not an original GLO corner)
1881-E.K. Robinson worked along the Town line in Sec. 32, T.33N., R.6W.
1885-E.K. Robinson set 1/4 stake during his work in Sec. 5, T.32N., R.6W. And witnessed:
Sugar 24" S45.75°W 65 lks; Hemlock 14" S29.5°E 67.5 lks.
1973-Charlevoix Abstract sketch along the Town line ---corner not in at this time.
1980-Danny Bongiovanni set a 5/8" rod during his survey in Sec. 5, T.32N., R.6W. And witnessed: 22" Maple S45°W 52.53';
St. Sign S80°W 33.37'; 24" Maple N60°W 42.65'; Conc. Mon. S45°E 46.68'--L.C.R.C. -(L.002, Pg. 106)
1980-Danny Bongiovanni set a 5/8" rod in his survey in Sec. 5 as mentioned above.
1995-John Ferguson found the 5/8" Bongiovanni rerod--no witnesses.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
D-1 North 1/4 corner Sec. 5, T.32N., R.6W.
1997-Arthur R. Ranger found the 5/8" Bongiovanni rerod and witnesses of record; Fits Robinson measurements to the East & West
Real well.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D-1 North 1/4 corner Sec. 5, T.32N., R.6W.
(Set a Charlevoix County Marker)
20" Maple N21°W 73.65'
7" Elm N87°E 51.55'
7" Elm S50°E 76.01'
P.P. S14°E 94.60'

Charlevoix Co. Surveyor
APPROVED
Signature Mary C. Feindt
Date: 12-11-97

THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEY. THIS MONUMENT IS ACCEPTED AS A CAREFUL AND FAITHFUL DETERMINATION OF THE POSITION OF THE CORNER.

Signed by Arthur R. Ranger Date 12/09/97
Surveyor's Michigan License No. 31601



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1993