

**SURVEY &
REMONUMENTATION**

OCT 18 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

96 OCT 10 AM 11:29

Charlene M. Coakley
REGISTER OF DEEDS

For corners in

<u>CHARLEVOIX</u> (County)	Located In:	Corner Code #
Public Land Survey	T 32NR 6W	<u>F-13</u>
	T 31NR 6W	F-1
	T ___ R ___	_____
	T ___ R ___	_____
Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

Arthur R. Ranger, in a field survey on May 18, 1995, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

Description of original monument and accessories and/or subsequent restoration:

- 13 1/4 corner common to Section 33, T.32N-R.6W & F-1 Section 4, T.31N-R.6W
- 156- E.D. Atwater set the Qr. Sec. Corner in his Resurvey and witnessed: Lynn 26" N54.5°E 48 lks; Elm 18" S55.5°W 33 lks.
- 178- E.K. Robinson, surveyor ran the South line of the southwest Quarter of Sec. 33, and set the West 1/8th stake.
- The State Highway Dept. Found a 1.5" pipe buried 10" deep in county gravel road and witnessed: 12" Elm N5°W 25.64'; 23" Maple N45°E 48.64'; 9" Maple S40°E 40.30'; Fnc. Post S20°W 34.19'

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 13 1/4 corner common to Section 33, T.32N-R.6W & F-1 Section 4, T.31N-R.6W
- 95- Arthur R. Ranger, surveyor found a 1/2" rod in the centerline of Pesek road E. & W., and found an old fence running South through the old cemetery to the South. There is also an old fence to the North. The corner lines up with both fences. The position of the corner fits the location of 1/8th line fence to the East within a foot. The old notes indicate that the county surveyors worked on the South line of Section 33.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 13 1/4 corner common to Section 33, T.32N-R.6W & F-1 Section 4, T.31N-R.6W
- placed with a Harrison monument.
- Maple N8°E 52.29'
- Maple S24°E 50.83'
- Maple S34°W 50.16'
- Maple N37°W 65.96'

Charlevoix Co. Surveyor
APPROVED
Signature *May C. Foydt*
Date: Oct 10, 1996

collateral evidence is local in nature, and is accepted as the best available evidence of the position of the original corner.

Recorded by *Arthur R. Ranger*
Surveyor's Michigan License No. 31601

Date 10/09/96



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

LIBER 003-36