

**SURVEY &
REMONUMENTATION**

OCT 18 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

96 OCT 10 AM 11:31

Charles M. Probert
REGISTER OF DEEDS

For corners in

<u>CHARLEVOIX</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>32NR 6W</u>	<u>H-13</u>
	T <u>31NR 6W</u>	<u>H-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Arthur R. Ranger, in a field survey on May 18, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-13 1/4 corner common to Section 34, T.32N-R6W & Section 3, T.31N-R.6W
1856- E.D. Atwater set the Qr. Sec. corner and witnessed: Beech 24" is the corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 1/4 corner common to Section 34, T.32N-R6W & Section 3, T.31N-R.6W
1995- Arthur R. Ranger, Surveyor found a 1/2" iron rod in line with an existing old fence to the North & South; The corner falls 8' North of the centerline of a 2-track road E. & W.; The stake is on the line between corners East and West. The 1/8th line fence to the West if doubled over for distance would only miss the above mentioned corner by 4'.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 1/4 corner common to Section 34, T.32N-R6W & Section 3, T.31N-R.6W
Replaced with a Charlevoix County Monument
8" Y. Birch N68°E 13.48'
10" Hemlock S20°E 22.27'
8" Maple S10°W 24.90'
13" Maple N42°W 15.58'

Charlevoix Co. Surveyor
APPROVED
Signature Mary C. Feendt
Date: October 10, 1996

The 1/2" rod found is based on local occupation, and is accepted as the best available evidence of the position of the original corner.

Signed by Arthur R. Ranger Date 10/09/96
Surveyor's Michigan License No. 31601



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995