

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 33 N.R. 4 W


Charlevoix COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 4 and 5

CORNER MONUMENT Left 1 1/2" pipe in place, 18" above ground

DATE MONUMENT PLACED AND WITNESSED August 17, 1961

WITNESSES TO CORNER.....



6" H. Maple - S86E - 29.1 feet

8" W. A sh - N86W - 6.0 feet

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in this area. Found an 1 1/2" pipe at corner as established by Marcus Schaaf in previous survey in 1930's. A ppears to have been a restoration of a 1905 survey as per records in county courthouse. 1905 Hemlock NBT stump in place NW, and sprout collar SW for ~~gaxkt~~ Basswood NBT. A lso the remains of one possible government BT in place. Checks acceptably for measurement with county records.

SURVEYOR'S SEAL

SIGNED Kenneth J. Ostling DATE 8/18/61
REGISTERED LAND SURVEYOR