

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 33 N.R. 4 W


Charlevoix COUNTY

DESCRIPTION OF CORNER Closing corner common to Sections 4 and 5,
on north boundary of township

CORNER MONUMENT Left 1 1/2" pipe in place

DATE MONUMENT PLACED AND WITNESSED August 17, 1961

WITNESSES TO CORNER.....



18" Elm - 857W - 103.8 feet

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in this area. Found 1 1/2" pipe at corner, as restored by Marcus Schaaf, FLS, in 1930's. Appears to be a restoration of a previous survey by county surveyor in 1909. Checks record measurements and line over corners south between 4-5 where the N1/8, the 1/4 corner and the SE corner of Section 5 can be identified as being the result of the 1909 survey.

Corner to Sections 32 and 33, T34N, R4W is 30 links east.

SURVEYOR'S SEAL

SIGNED Kenneth Petting DATE 8/18/61
REGISTERED LAND SURVEYOR