

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 33 N.R. 4 W


Charlevoix COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 3-4-9-10

CORNER MONUMENT Set 1" pipe with 4" Aluminum cap, 6" below surface

DATE MONUMENT PLACED AND WITNESSED 8/31/61

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

|            |   |      |   |           |
|------------|---|------|---|-----------|
| 7" R. Pine | - | N64W | - | 29.6 feet |
| 8" R. Pine | - | S41W | - | 29.4 feet |
| AND 7" Elm | - | S57E | - | 14.2 feet |

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in this area. Found good stake point below road surface by retracing old 1905 survey. Large boulder in place but covered with dirt for NE witness of record, and stump of NW Hemlock in place. Checks record measurement to section corners west and north. Perpetuates corner as established in 1880 state road survey.

SURVEYOR'S SEAL

SIGNED Kenneth J. Betting DATE 9/22/61  
REGISTERED LAND SURVEYOR