

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 33 N.R. 4W


Charlevoix COUNTY

DESCRIPTION OF CORNER 1/4 corner on north side section 6.

CORNER MONUMENT Drove 1" x 24" pipe.

DATE MONUMENT PLACED AND WITNESSED 12-6-61

WITNESSES TO CORNER.....



12" Elm - S 55 E - 27.7 feet

12" Elm - S 74 W - 44.2 feet

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between section corners while making a survey in this area. Set corner $17\frac{1}{2}$ links west of 1/4 corner on south side Sec. 31, T34N R4W. No previous corner.

1/4 corner on south side, Sec. 31, T34N R4W is $17\frac{1}{2}$ links east.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE 12/12/61
REGISTERED LAND SURVEYOR