

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 33 N. R. 4W


Charlevoix COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 8 - 17

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 11-22-61

WITNESSES TO CORNER.....



7" Twin Balsam - N 8 W - 16.2 feet

5" Balsam - S 87½ E - 18.2 feet

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established while making a survey in this township. Set corner midpoint, on line between section corners. Could not positively identify 1902 NBT's although several stumps in vicinity. Checks 1902 record measurements to stream crossings and swamp edge.

SURVEYOR'S SEAL

SIGNED Kenneth J. Oething DATE 11/28/61
REGISTERED LAND SURVEYOR