

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 33 N. R. 4W


Charlevoix COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 8 - 9 - 16 - 17

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 11-22-61

WITNESSES TO CORNER.....



8" W. Ash - N 18 E - 5.8 feet

7" W. Ash - S 4 E - 43.9 feet

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established while making a survey in this township. Set corner by proportionate measurement for latitude between section corner north and center of 1/4 line road south. The longitudinal position determined by a measurement of record for south line of Section 8 in 1902 survey by County Surveyor. While this location makes Section 8 about 4 chains long, and Section 9 about 3 chains short, it is noted that this situation was found to exist in the 1902 survey when the U.S. B.T's. were identified. Measurements on the north side of Section 8 and the south side of Section 17 would seem to support this method of restoration.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE 11/28/61
REGISTERED LAND SURVEYOR