

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>33</u> N. <u>4</u> E. R. <u>4</u> W.	<u>C-12;</u>
2. PROPERTY CONTROLLING IN SECTION <u>32</u>	T. <u>33</u> N. <u>4</u> E. R. <u>4</u> W.	<u>1</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 19, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
 C-12 - Restored  $\frac{1}{4}$  cor. to Sec's 31&32 at old cor. fn. post (good B-W on fn. posts N&W crooked B-W in trees & on posts to E). Fits straight line bet. Sec. cor's to N&S & is within 10' of being mid-way.

1 - Re-estab. W  $\frac{1}{8}$  corner on south line of Sec. 29 midway & on line between fd. S $\frac{1}{4}$  cor. & fd. SW cor. of Sec. 29. Corner falls in ctr. of E-W gravel road.

A N-S fn. to south is  $\frac{1}{4}$ '± east. A N-S fn. to north (starts approximately 500' north) is 1'± east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>C-12</u>			<u>1</u>		
Set DNR Mon. & Cedar post at fn. cor.			Drove 5/8" x 34" rerod w/RLS cap		
6" Maple	S67°E	34.9'	19" Maple	S42°E	103.65'
3" Maple	S26°E	31.2'	20" Maple	N15°E	37.27'
12" Maple	S50°W	7.5'	8" Spruce	N68°E	92.08'
8" Maple	N45°E	8.0'	E-W R.O.W. fn.	South	36'
Fd. Schaaf pipe (removed)	N27°22'E	13.4'	E-W R.O.W. fn.	North	33'
			Set cedar post w/loc tag	South	33'


SIGNED BY Carl F. Roser 02-07-86 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ CHARLEVOIX COUNTY