

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>33</u> N. <u>04</u> W. <u>04</u>	C-9, D-9
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on DECEMBER 6, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- C-9 FD & ACCEPTED LARGE BOAT SPK (AS WITNESSED BY RLS M.FEINDT) FOR NW COR OF SEC 29. FITS SURVEY & SEC SUB'N OF SEC 29 BY E.A.ROBINSON, DATED 1902; SEE CHANDLER BK PGS 4-9 & 59. COR FALLS IN CTR OF N-S GRAVEL RD AND FITS U.S. (G.L.O.) TIE SOUTH TO SOUTH EDGE OF STREAM OF 528' REC & MEA. E.A.R'S SEC. 29 DRAWING ALSO SAYS SEC LINE RD ON W LINE OF SEC. 29.
 - D-9 RESTORED 1/4 COR COMMON TO SEC'S 20 & 29 MID-WAY & ON LINE BETW NE & NW COR'S OF SEC 29. FITS E.A.ROBINSON OVER-ALL SUR & SEC SUB'N OF SEC 29, DATED JAN 1902; CHANDLER BK, PGS 4-9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FD LARGE B SPK; REPLACED W/ 5/8 X 34" REROD W/RLS CAP.	C-9	DROVE 1" X 50" PIPE W/DNR CAP & SET CEDAR POST.	D-9
10" TAMARACK N60°E 30.50		9" CEDAR N58°W 17.2'	
9" TAMARACK S40°E 40.45		8" CEDAR S30°W 25.9'	
SET CED POST W/LOC TAG. EAST 20.'		10" WHITE PINE S70°E 13.4'	
CTR OF 20" WIDE STREAM SOUTH 514'(±2')		8" CEDAR N22°E 24.1'	

SIGNED BY Carl F. Roser 02-07-86 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

CHARLEVOIX COUNTY