

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>33</u> N. <u>0.</u> , R. <u>4</u> W.	E-6; E-7 ✓
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____, R. _____ E. _____ S. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____ S. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 4, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a

B. Decree of a Court of law:
(Continued):

~~Acc Description of original monument locations and descriptions of structures~~

E-7 - (Continued)

Records at courthouse (Jury Room) Large Liber 1, page 233: New pine 24,N54W 37½ links New pine 20,N54E 45 links. Two definite pine stump remains evident that fit Robinson's data. E.K. Robinson says "old bearing tree's dead."

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

E-6 - Found & accepted 3/4" pipe for 1/4 corner common to Sec. 16 & 17. Fits E.A. Robinson survey of Sec. 17, dated July 1902, every 1/4 mile west across E-W 1/4 line of Sec. 17 & E.K. Robinson East 1-mile to E½ corner of Sec. 16, dated 1886. See Chandler Field Book, pgs. 10-17 and Book 116, pg. 14 old county survey records in Jury Room at courthouse also fits L. Feindt survey west 1-mile along E-W 1/4 line of Sec. 17 & J. Ferguson survey East one mile to E½ corner of Sec. 16. Cor. is 2'± N. of ctr. of E-W gravel rd. & in approx. line with old fn. to north.

E-7 - Fd. & accepted 3/4" pipe that fit R.L.S., Mary Feindt wits. Also fits E.K. Robinson's Nov. 1887, Pine (stump remain's) N.B.T.s as noted in old County Surveyor's (continued)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6			E-7		
Found 3/4" pipe			Fd. 3/4" pipe; replaced w/DNR mon & set cedar post		
14" Maple	S70°E	77.18'	9" White Birch	N53°W	28.38'
23" Maple	S10°W	27.65'	14" Aspen	N40°E	40.54'
Power Pole	N70°E	83.10'	8" Maple	S46°E	41.9'
Old Cor Fn post	North	24.07'	4" Ironwood	S42°W	36.1'

SIGNED BY Carl F. Roser 02-07-86 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:


SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CHARLEVOIX COUNTY