

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>33</u> N. <u>0.</u> R. <u>4</u> W. <u>0.</u>	<u>B-7; C-7</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 3, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- B-7 - Fd. & accepted Marcus Schaaf 2" pipe at old fn. corner (fn's E-W-S). Fits E.K. Robinson mea.'s of N. line of Sec. 19 very close. See Bk. 20, pg. 66, dated 1890 & 1891.
- C-7 - Fd. 3/4" x 39" pipe, by E.A. Robinson, surrounded by rocks & 2" x 36" pipe w/conc. base along side (24" out of ground), by Marcus Schaaf. Re-set M.S. 2" pipe down in ground in place of E.A. Robinson 3/4" pipe (2" pipe 6"± out of ground) and drove E.A. Robinson's 3/4" pipe down inside 2" pipe. Hillside slopes down to N. See E.A. Robinson's notes - Chandler Field Bk., page 62, Sept. 4, 1913.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

	B-7		C-7		
Fd. 2" pipe & set cedar post w/loc tag			Fd. 3/4" pipe by E.A.R. & 2" pipe by M.S. & set cedar post w/loc tag		
8" Maple	N56°E	21.5'	9" Maple	N10°W	21.4'
11" Maple	S55°E	6.2'	5" Maple	N42°E	12.0'
7" Maple	S46°W	10.1'	3" Ironwood	S70°E	19.0'
10" Ash	N25°W	16.0'	6" Maple	S70°W	9.1'

SIGNED BY Carl F. Roser 02-07-86 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ CHARLEVOIX COUNTY