

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>33</u> N. <u>4</u> E. <u>W.</u>	<u>A-8;</u>
2. PROPERTY CONTROLLING IN SECTION <u>19</u>	T. <u>33</u> N. <u>4</u> E. <u>W.</u>	<u>10</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 3, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-8 - Found & accepted "T" iron by Mary Feindt for W 1/4 corner of Section 19. Ctr. of old N-S tote road is West 2'±.
- 10 - Drove 5/8" x 34" rerod for SW corner of NW¼ of SW¼ of Section 19; per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	<u>A-8</u>		<u>10</u>			
Fd. M.F. "T"iron, added DNR mon. & set cedar post				Drove 5/8" x 34" rerod w/RLS cap & set cedar post w/loc tag		
*16" White Pine	N45°E	29.35'		12" Cedar	N50°W	29.2'
*13" Cedar	S85°E	25.31'		7" Cedar	S70°E	25.5'
* 4" Balsam	S10°W	29.47'		14" Cedar	N85°W	19.4'
5" Ash	S70°W	16.9'		Ctr old N-S tote rd	West	6'±

\*M. FEINDT WITS (FACE NAILS W/CAP #3920)

SIGNED BY Carl F. Roser 02-07-86 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ CHARLEVOIX COUNTY