

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>33</u> N. <u>•</u> , R. <u>4</u> W. <u>•</u>	<u>B-8;</u>
2. PROPERTY CONTROLLING IN SECTION <u>19</u>	T. <u>33</u> N. <u>•</u> , R. <u>4</u> W. <u>•</u>	<u>4; 5; 15</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 3, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

C. (Continued):

<u>5</u>	<u>15</u>
Drove 5/8" x 34" reroed w/RLS cap & set cedar post w/loc tag	Drove 5/8" x 34" reroed w/RLS cap & set cedar post w/loc tag
16" Red Pine N70°E 17.33'	19" Green Elm N25°E 53.62'
16" Red Pine S25°E 24.40'	12" Apple Tree N65°E 129.65'
15" Red Pine S30°W 24.65'	Fd. sq. conc. mon. N66°42'E 109.02'
Fd 1 1/2" pipe S71°07'E 65.45'	Fd. L.F. T-iron S53°50'E 0.97'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
**B-8 - Established center of Sec. 19 at intersection of 1/4 lines.**

- 4 - Estab. ctr. of NW 1/4 of Sec. 19 (prorated to G.L.O. plat, run-out Sec.) per std. B.L.M. instructions.
- 5 - Drove 5/8" x 34" reroed for SW corner of NW 1/4 of NE 1/4 of Sec. 19; per std. B.L.M. instructions.
- 15 - Drove 5/8" x 34" reroed for SW corner of SE 1/4 of SW 1/4 of Sec. 19; per std. B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>B-8</u>	<u>4</u>
Drove 5/8" x 34" reroed w/RLS cap & set cedar post w/loc tag	Drove 5/8" x 34" reroed w/RLS cap & set cedar post w/loc tag
6" Cedar N80°W 3.1'	24" White Pine S50°E 9.3'
10" Cedar N30°E 17.2'	10" Cedar N72°W 14.7'
28" White Pine N70°E 30.5'	6" Cedar S70°W 1.3'
12" Cedar S45°E 13.5'	

SIGNED BY Carl F. Roser 02-07-86 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ CHARLEVOIX COUNTY