

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>33</u> N. <u>0.</u> , R. <u>4</u> W. <u>0.</u>	<u>C-8</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. _____, R. _____ E. _____ S., R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. _____ S., R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 21, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 C-8 - Restored 1/4 cor. common to Sec. 19 & 20 mid-way & on line between fd. Sec. corners to N&S. E.K. Robinson (Jan 1891-Bk. 20, pgs. 67-70) re-estab. SE cor. Sec. 19 at 8.00 chs. N. (G.L.O.) of creek crossing to south, then chained N. & made calc. 1/4 cor. to Sec. 19&20 at s.p. 41.83½ chs. (in N-S rd-crossing) & chained (continued) N. to Sec. cor. to Sec. 17-18-19-20 at 83.67 chs. (½ = 41.83½). In Sept. 1913 (Field Bk., Chandler pgs. 59 & 62) E.A. Robinson chained the same mile (E. line Sec. 19) bet. E.K. Robinson's Sec. corners at 82.97 chains (5476'). We mea. the mile at 5480.39' & set E 1/4 Sec. 19 S.P. since Robinson could not recover Gov't. 1/4 corner in 1891 & 1913 (rd in swp).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	<u>C-8</u>	
Drove 5/8" x 34" rerod w/RLS cap - at West edge of N-S gravel rd. in small curve		
Fd. B. spk.	S10°06'E	85.77'
12" Spruce	N70°E	29.07'
9" Cedar	N60°E	76.95'
10" Cedar	S40°E	67.30'
Ctr of E-W creek (48" C.M.P.)	South	141'±
Set cedar post	West	20'
Ctr gravel rd in curve to go over CMP	East	10'±
Ctr N-S gravel rd to N&S (eye-ball)	East	6'±

SIGNED BY Carl F. Roser 02-07-86 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CHARLEVOIX COUNTY

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET