

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>33</u> N. <u>04</u> W. <u>04</u>	E-9, E-10
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 6, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-9 - Restored NE Cor. of Sec. 29 by Double proportion to U.S. (G.L.O.) which equals D.P. to E.A. Robinson & E.K. Robinson. See E.K. Robinson, large "Co. Surveyor's Liber 1, pgs. 233 & 235", dated Nov. 1887; & E.A. Robinson, "Chandler Field Book, pgs. 4-9", dated Jan. 1902; notes on file at Jury Rm. in Ct. House. D.P. is 1-mile N-S-E-W to fd. cor's, same as Robinson. Ctr. of gravel road (NNW-SSE) is recent cut-over area no large trees available for N.B.T.'s. 185'± west
- E-10 - Re-estab. 1/4 cor. common to Sec's 28 & 29 mid-way & on line between NE & SE Cor's of Sec. 29. Fits E.A. Robinson survey of Sec. 29; Chandler Bk., pgs. 4-9, on file at Jury Room in courthouse.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	E-9			E-10	
Set DNR mon. & cedar post w/rocks along side monument				Drove 1" x 52" pipe w/DNR cap & set ced. post	
2" P. Cherry	N10°E	60.1'		11" Cedar	N48°W 20.1'
3" Maple	S86°E	38.5'		8" Cedar	N80°E 5.6'
3" Maple	S48°W	23.5'		10" Hemlock	S04°E 25.9'
4" Balsam	S80°W	75.0'		8" Cedar	S56°W 1.6'

SIGNED BY Carl F. Roser 02-07-86 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

CHARLEVOIX COUNTY

