

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>33</u> N. <u>4</u> R. <u>4</u> W.	H-12;
2. PROPERTY CONTROLLING IN SECTION <u>34</u>	T. <u>33</u> N. <u>4</u> R. <u>4</u> W.	3
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 23, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

3 - Fd. 3" dia. by 18" deep stake shadow with bark on outer edge from one E.A. Robinson (1905) B.T. remain's; Sugar 26" (stump hole w/roots), S74 3/4°E, 21.5'. Fits E.A. Robinson Sur. & Sec. Sub'n. of Sec. 34; notes on file at Jury Room in Gov't. Bldg., Chandler Book, pg. 29. N-S random is 2.15' West.

H-12 - Fd. 3/4" pipe with black-smith made eye-bolt inside same for ctr. of Sec. 34. Fits E.A. Robinson B.T., Sugar Shade Tree 8 (fd. sugar stump), S19 1/2°W, 19.8'. See Chandler Book, pg. 27 (1905), on file at Jury Room in Gov't. Bldg. Fits E.A. Robinson Sur. & Sec. Sub'n. of Sec. 34. Corner is 9' West of ctr. of N-S sand & gravel road and in line with fence remains to East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	<u>3</u>		<u>H-12</u>
Drove 5/8" x 34" rerod w/RLS cap in fd. stake hole remains; added cedar post w/loc tag			Fd. eye bolt in 3/4" pipe; add. RLS cap. w/loc tag & set cedar post
15" Oak N54°E 8.1'			12" Maple S50°W 6.36'
4" Maple S48°E 7.8'			13" Red Pine N84°W 31.02'
11" Oak S22°W 12.6'			9" Maple N74°E 83.12'
			5" Maple S80°E 35.32'

SIGNED BY Carl F. Roser 02-07-86 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

CHARLEVOIX COUNTY

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 26, 1971  
REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET