

99 NOV 11 PM 2:57

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS

For corners in  
 CHANDLER TWP

CHARLEVOIX  
 (County)

Located In: Corner Code #

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>33N</u> R <u>4 W</u> | <u>E-1</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

RECORDED

FEB 02 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, JAMES E. EVANS, in a field survey on MARCH 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-1 SECTION CORNER COMMON TO SECTIONS 4 & 5 T33N-R4W  
 GENERAL LAND OFFICE  
 Set post  
 Sugar 12" S86°E 6 Links (3.96')  
 Lynn 10" S70°W 34 Links (22.44')  
 Aug 22, 1841  
 By: Ch. W. Cathcart D.S.

Charlevoix Co. Surveyor  
**APPROVED**  
 Signature Mary C. Ferndt  
 Date: Nov. 11, 1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1 SECTION CORNER COMMON TO SECTIONS 4 & 5 T33N-R4W

E. A. Robinson July 1909	Kenneth J. Ostling PS #10068
Set Cedar stake 3 ft in ground	Aug. 18, 1961 Found 1 1/4" pipe as
B. Ash 28" N12°W 42 lks (27.72') (1)	restored by Marcus Schaff. Appears to be
	a restoration of 1909 survey.
	18" Elm S57°W 103.8' (2)

Found 1 1/4" bent pipe.

Distance to corner D-1 Measured 2574.93' (GLO = 2640.0')  
 Distance to corner F-1 Measured 2608.30' (Robinson = 2608.98' GLO = 2640.0')  
 Distance to E-13 T34N R4W 19.57' (GLO = 19.80')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1 SECTION CORNER COMMON TO SECTIONS 4 & 5 T33N-R4W

Replaced pipe with Charlevoix County cast iron monument.

WITNESSES:	Fence post	N01°E	287.26'	Set pk & cap in top
	12" Spruce	N88°W	224.34'	Set pk & cap in North side
	8" W. Birch	S15°W	134.85'	Set pk & cap in East side
	DNR disk	N90°E	19.57'	Record = 19.80'

And is accepted as the best available evidence of the position of the original corner.

Signed by [Signature]

Date 11-11-99

Surveyor's Michigan License No. 22431

