

NOV 2 1 1997

COMMISSION

STATE OF MICHIGAN  
COUNTY OF CHARLEVOIX  
RECEIVED FOR RECORD

97 OCT -9 PH 3: 26

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Charles M. Perkins*  
REGISTER OF DEEDS

For corners in

CHARLEVOIX  
(County)

Located In: Corner Code #

1. Public Land Survey

T 33N R 4W G-1

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, James E. Evans, in a field survey on Sept 2, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
G-1 Corner common to Sections 3 and 4 T33N - R4W

GLO: Set post Mich. Dept of Conservation  
Lynn 6" S60°E 12 lks. ( 7.92') 8-25-59 By Kenneth Ostling RLS #10068  
Sugar 6" S36°W 9 lks ( 5.94') Found 1/2" X 2" iron bar  
8-19-1841 By Ch. W. Catheart D.S. Set 1" pipe with 4" brass cap  
8" Maple S40°E 8 lks. ( 5.28')  
7" Maple S48°W 58 lks (38.28')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
G-1 Corner common to Sections 3 and 4 T33N - R4W

Found bent Dept of Conservation brass capped pipe; bottom appears to be ok. Pipe is on line between F-13 and G-13 of T34N-I and is 7 ft South of the center line of an East and West gravel road.

Found blazed 14" Maple S28°E 5.55' (R= 5.28')  
Found blazed 11" Maple S48°W 38.82' (R=38.28')

GLO to H-1 = 2640' MEAS = 2622.16'  
GLO to F-1 = 2640' Comp = 2601.29'  
GLO to G-13 = 33.00' Comp = 33.00'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
G-1 Corner common to Sections 3 and 4 T33N - R4W

REPLACED BENT PIPE WITH CHARLEVOIX COUNTY MONUMENT.

22" MAPLE N52°E 35.55' SET NAIL & CAP #22431 IN NW SIDE (This was used as witness to G-13 in 1959)  
14" TW. MAPLE S28°E 5.55' SET NAIL & CAP #22431 IN WEST SIDE (R=5.28')  
11" TW. MAPLE S48°W 38.82' SET NAIL & CAP #22431 IN NORTH SIDE (R=38.28')  
10"/16" TW. MAPLE N40°W 28.01' SET NAIL & CAP #22431 IN SE SIDE

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *James E. Evans*

Date 10-9-1997

Surveyor's Michigan License No. 22431

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		
3												
4		7		8		9		10		11		1
5												
6		18		17		16		15		14		1
7												
8		19		20		21		22		23		2
9												
10		30		29		28		27		26		2
11												
12		31		32		33		34		35		3
13												

Charlevoix Co. Surveyor  
APPROVED  
Signature *James E. Evans*  
Date: 10-9-1997

