

REMONUMENTATION

NOV 21 1997

COMMISSION

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

97 OCT -9 PM 3:28

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Mary C. Fleenor
REGISTER OF DEEDS

For corners in

CHARLEVOIX
(County)

Located In: Corner Code #

- 1. Public Land Survey T 33N R 4W I-1
- 2. Property Controlling In Section S T R
- 3. Miscellaneous Property in Sec. S T R
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

I, James E. Evans, in a field survey on Sept 2, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

A. Description of original monument and accessories and/or subsequent restoration:

I-1 Corner common to Sections 2 and 3 T33N - R4W
 GLO: Set post Mich. Dept of Conservation
 Elm 10" S33°E 8 lks. (5.28') 8-11-59 By Kenneth Ostling RLS #10068
 Elm 6" S45°W 16 lks (10.56') Found 1" pipe established by Marcus Schaaf, RLS
 8-21-1841 By Ch. W. Cathart D.S. 16" Elm S11°W 37.3'
 10" Elm S73°E 66.2'
 Orlando Doyle RLS #7319
 Jan 1968.
 Same witnesses as Dept. of Conservation

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1 Corner common to Sections 2 and 3 T33N - R4W
 Found 1" pipe in intersection of East/West and North gravel road.
 Did not find any old witnesses. Pipe is 0.36 ft North of township line.
 GLO to J-1 = 2640' MEAS = 2645.46'
 GLO to H-1 = 2640' Comp = 2624.53'
 GLO to I-13 = 19.80' Comp = 19.97'

Charlevoix Co. Surveyor
APPROVED
Signature Mary C. Fleenor
Date: 10-9-1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 Corner common to Sections 2 and 3 T33N - R4W
REPLACED 1" PIPE WITH CHARLEVOIX COUNTY MONUMENT.
 18" R. PINE N48°E 72.50' SET NAIL & CAP #22431 IN SOUTH SIDE (This was used as witness to I-13 in 1959)
 RR TIE FENCE POST/SIGN POST (WEBER RANCH) S22°E 14.14' SET NAIL & CAP #22431 IN EAST SIDE
 CEDAR POST (At cattle crossing) N55°W 17.57' SET NAIL & CAP #22431 IN NORTH SIDE
 36" DIAMETER ROCK N05°W 59.01' SET CHISELED "X" IN TOP OF ROCK
 FOUND 3/4" PIPE AT I-13 (T34N-R4W) S89°E 19.97'

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *James E. Evans*

Date 10-9-1997

Surveyor's Michigan License No. 22431

