

Survey &
REMONUMENTATION

NOV 21 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

97 OCT -9 PH 3:30

Charlotte M. Condon
REGISTER OF DEEDS

For corners in

CHARLEVOIX
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>33N</u> R <u>4W</u> | <u>K-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling In Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

I, James E. Evans, in a field survey on Sept 2, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
K-1 Corner common to Sections 1 and 2 T33N - R4W

GLO: Set post	Mich. Dept of Conservation
Sugar 10" S40°W 12 lks. (7.92')	7-28-60 By Kenneth Ostling RLS #10068
Sugar 10" S40°E 32 lks (21.12')	Found 1 1/4" pipe
8-19-1841 By Ch. W. Cathart D.S.	7" Elm S15°E 30 lks. (19.8')
	7" Maple S54°W 63.5 lks (41.91')

Orlando Doyle RLS #7319
Jan 1968
Same witnesses as Dept. of Conservation

Charlevoix Co. Surveyor
APPROVED
Signature *Mary S. Fennell*
Date: 10-9-1997

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
K-1. Corner common to Sections 1 and 2 T33N - R4W

FOUND 1 1/4" PIPE DISTURBED (LYING FLAT UNDERGROUND) 6 FT NORTH OF CENTER LINE OF GRAVEL ROAD
FOUND OLD STUMP S17°E 19.73' TO FACE (R=19.8')
FOUND BLAZED 12" MAPLE S53°W 41.90' (R=41.91')

SET CHARLEVOIX COUNTY MONUMENT 13.20' (20 lks) WEST OF K-13 (DNR MON) AND ON LINE WITH K-13 AND I-13.
GLO TO J-1 = 2640' CA&E 1975 = 2644.64' MEAS = 2644.66'
GLO TO K-13 = 13.20' MEAS = 13.20'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-1 Corner common to Sections 1 and 2 T33N - R4W

SET CHARLEVOIX COUNTY MONUMENT AS DESCRIBED ABOVE.
11" ELM N60°E 38.52' SET NAIL & CAP #22431 IN NORTH SIDE (FOUND BLAZE USED AS WITNESS TO K-13)
14" & 10" TW. MAPLE S66°E 41.67' SET NAIL & CAP #22431 IN SW SIDE
12' MAPLE S53°W 41.90' SET NAIL & CAP #22431 IN NW SIDE (FOUND OLD BLAZE IN FACE)
11" MAPLE N22°W 39.22' SET NAIL & CAP #22431 IN WEST SIDE (FOUND OLD BLAZE IN FACE)
DNR MONUMENT @K-13 DUE EAST 13.20'

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *James E. Evans*
Surveyor's Michigan License No. 22431

Date 10-9-1997

