

SURVEY & REMONUMENTATION

FEB 04 1999

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

98 NOV 13 PM 3:54

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Charles M. Crabtree
REGISTER OF DEEDS

For corners in
HANDLER TWP

CHARLEVOIX
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>33N</u> R <u>4 W</u>	<u>M-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, JAMES E. EVANS, in a field survey on OCTOBER 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-1 NE CORNER SECTION 1 T33N-R4W
GENERAL LAND OFFICE
Set post
Maple 10" N25°E 12 Links (7.92')
Maple 8" S65°W 10 Links (6.60')
May 22, 1840
By: John Mullett, D.S.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-1 NE CORNER SECTION 1 T33N-R4W

Found rebar in the center line of North County Line Road. No identification or witnesses found. Inquired to Emmet County and Cheboygan County with no success. DNR notes from 1958 indicate this corner may have been set by Marcus Schaff. DNR makes reference to corner being .75 chains (49.5') East of a plantation. The found rebar is approx. 50 feet East of the edge of a pine plantation to the North.

Charlevoix Co. Surveyor

APPROVED

Signature Mary C. Fenrott

Date: Nov 12, 1998

Distance to corner L-1 Measured 2588.26' (DNR = 2574.00')
Distance to corner M-2 Measured 2657.20' (GLO = 2640.00')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1 NE CORNER SECTION 1 T33N-R4W

Set cast iron Charlevoix County monument at location of found rebar.


WITNESSES: 17" R Pine N71°E 64.96' Set nail and cap in South side
23" Cherry S50°E 34.65' Set nail and cap in West side
Wood sign post N80°W 94.01' Set nail and cap in South side
16" Cherry S71°W 207.20' Set nail and cap in SE side

And is accepted as the best available evidence of the position of the original corner.

Signed by *James E. Evans*

Date 11-12-98

Surveyor's Michigan License No. 22431



LIBER 003 PAGE 201

MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 25, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995