

FEB 04 1999

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

SECTION

LAND CORNER RECORDATION CERTIFICATE 98 NOV 13 PM 3:55
Filing Requirement of Act 74, Mich. P.A. 1970

Charles M. Cook
REGISTER OF DEEDS

For corners in
CHANDLER TWP.

CHARLEVOIX
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 33N R 4 W M-2
- T R
- T R
- T R
- 2. Property Controlling in Section S T R
- S T R
- 3. Miscellaneous Property in Sec. S T R
- S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, JAMES E. EVANS, in a field survey on OCTOBER 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
M-2 QUARTER CORNER COMMON TO SEC 1 T33N-R4W and SEC 6 T33N-R3W
GENERAL LAND OFFICE
Set 1/4 Sec. post
Maple 10" S72°E 29 Links (19.14')
Maple 10" N37°W 14 Links (9.24')
May 22, 1840
By: John Mullett D.S.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-2 QUARTER CORNER COMMON TO SEC 1 T33N-R4W and SEC 6 T33N-R3W
Found no corner or evidence of original corner.
No occupation available.

Distance to corner M-1 Measured 2657.20' (GLO = 2640.0')
Distance to corner M-3 Measured 2657.20' (GLO = 2640.0')

Charlevoix Co. Surveyor
APPROVED
Signature Mary C. Fenwick
Date: Nov 12 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-2 QUARTER CORNER COMMON TO SEC 1 T33N-R4W and SEC 6 T33N-R3W
Set cast iron Charlevoix County monument half way on line between M-1 and M-3.

WITNESSES: 8" Cherry S68°W 22.13' Set nail and cap in North side
11" Elm S30°W 8.78' Set nail and cap in East side
7 Ironwood N12°W 11.56' Set nail and cap in West side
14" Cherry N53°W 47.27 Set nail and cap in South side

And is accepted as the best available evidence of the position of the original corner.

Signed by *James E. Evans*
Surveyor's Michigan License No. 22431

Date 11-12-98

License 003-202

