

SURVEY & REMONUMENTATION

FEB 04 1999

STATE OF MICHIGAN COUNTY OF CHARLEVOIX RECEIVED FOR RECORD

98 NOV 13 PM 3:56

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Charlene M. [Signature] REGISTER OF DEEDS

For corners in CHANDLER TWP

CHARLEVOIX (County)

Located In:

Corner Code #

- 1. Public Land Survey T 33N R 4 W M-3
2. Property Controlling in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

Grid table with columns A-L and rows 1-13. Contains numbers 1-36 in a grid pattern.

I, JAMES E. EVANS, in a field survey on OCTOBER 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: M-3 CORNER COMMON TO SEC 1 & 2 T33N-R4W and SEC 6 & 7 T33N-R3W GENERAL LAND OFFICE 28" Maple for corner May 22, 1840 By: John Mullett D.S.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: M-3 CORNER COMMON TO SEC 1 & 2 T33N-R4W and SEC 6 & 7 T33N-R3W

Found no corner or evidence of original corner. No occupation available.

Distance to corner M-2 Measured 2657.20' (GLO = 2640.0') Distance to corner M-4 Measured 2657.20' (GLO = 2640.0')

Charlevoix Co. Surveyor APPROVED Signature Mary C. Ferndt Date: Nov. 12, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: M-3 CORNER COMMON TO SEC 1 & 2 T33N-R4W and SEC 6 & 7 T33N-R3W

Set cast iron Charlevoix County monument half way on line between M-2 and M-4.


- WITNESSES: 17" R Pine N82°E 25.23' Set nail and cap in South side 7" Basswood S58°E 18.15' Set nail and cap in North side 10" Basswood S39°W 23.98' Set nail and cap in NW side 11" Maple N02°W 32.66' Set nail and cap in East side

And is accepted as the best available evidence of the position of the original corner.

Signed by [Signature] Surveyor's Michigan License No. 22431

Date 11-12-98

LIBEX 003 203



APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983 REVISED OCT., 1995