

SURVEY &
REMONUMENTATION

FEB 04 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

98 NOV 13 PM 3:59

SECTION

For corners in
CHANDLER TWP

CHARLEVOIX
(County)

Located In:

Corner Code #

Charles M. Barber
REGISTER OF DEEDS

1. Public Land Survey T 33N R 4 W M-6
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, JAMES E. EVANS, in a field survey on OCTOBER 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
M-6 QUARTER CORNER COMMON TO SEC 13 T33N-R4W & SEC 18 T33N-R3W
GENERAL LAND OFFICE
Set 1/4 Sec. post
Beech 10" N45°W 29 Links (19.14')
Beech 8" S28°E 27 Links (17.82')
May 22, 1840
By: John Mullett D.S.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-6 QUARTER CORNER COMMON TO SEC 13 T33N-R4W & SEC 18 T33N-R3W
Found no corner or evidence of original corner.
No occupation available.

Distance to corner M-5 Measured 2657.20' (GLO = 2640.0')
Distance to corner M-7 Measured 2657.20' (GLO = 2640.0')

Charlevoix Co. Surveyor
APPROVED
Signature *Mary C. Ferrell*
Date: Nov 12 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-6 QUARTER CORNER COMMON TO SEC 13 T33N-R4W & SEC 18 T33N-R3W
Set cast iron Charlevoix County monument half way on line between M-5 and M-7.

WITNESSES: 28" W. Pine S80°E 25.74' Set pk and cap in South side
9" Maple N68°W 10.16' Set spike in East side
30" W. Pine S67°W 45.70' Set nail and cap in South side
30" W. Pine N82°W 42.69' Set pk and cap in South side


And is accepted as the best available evidence of the position of the original corner.

Signed by *James E. Evans*

Date 11-12-98

Surveyor's Michigan License No. 22431

License 003-206



MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1993