

**SURVEY &  
RECORD DOCUMENTATION**

OCT 18 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF CHARLEVOIX  
RECEIVED FOR RECORD

96 OCT 14 AM 10:31

*Charlotte M. Pirocher*  
REGISTER OF DEEDS

For corners in

Cheboygan

Charlevoix &  
(County)

Located in:

Corner Code #

- |                                    |                |            |
|------------------------------------|----------------|------------|
| 1. Public Land Survey              | T33N R4W       | <u>M-7</u> |
|                                    | T33N R3W       | A-7        |
|                                    | T___ R___      | _____      |
|                                    | T___ R___      | _____      |
| 2. Property Controlling in Section | S___ T___ R___ | _____      |
|                                    | S___ T___ R___ | _____      |
| 3. Miscellaneous Property in Sec.  | S___ T___ R___ | _____      |
|                                    | S___ T___ R___ | _____      |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, James E. Evans, in a field survey on Oct. 2, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

**M-7 CORNER COMMON TO SEC 13 & 24 T33N-R4W and SEC 18 & 19 T33N-R3W**

GLO: Set post	June 1970 Survey by Charlevoix
30" Sugar S60°W 3 lks (1.98')	Abstract & Engineering
10" Beech N82°E 11 lks (7.26')	Found 2" pipe 2 ft. above ground
by John Mullett in 1840	7" Basswood North 7.00'
	5" Maple S15°W 9.00'
	10" Elm N83°E 12.30'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" gas pipe with 6" concrete base

Found 10" Basswood N2°E 7.00'  
Found 7" Maple S13°W 9.00'  
Found Elm Stump N83°E 12.30'

GLO to M-8 = 2640'  
C.A.&E. 1970 = 2660.27  
Meas = 2660.35'

Charlevoix Co. Surveyor  
**APPROVED**  
Signature *Mary C. Fendt*  
Date 10-10-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced pipe with Charlevoix County cast iron monument.

10" Basswood N2°E 7.19' set nail & cap #22431 in West side (Rec= 7.00')  
7" Maple S13°W 8.92' set nail & cap #22431 in East side (Rec= 9.00')  
5" Maple S73°E 15.07' set nail & cap #22431 in SE side  
7" Maple N71°W 26.58' set nail & cap #22341 in NE side

And is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by *James E. Evans*  
Surveyor's Michigan License No. 22431

Date 10-10-96

