

**SURVEY &
REMONUMENTATION**

DEC 16 1996

COMMISSION

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
REGISTERED

96 NOV 13 PM 4:52

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Charlene M. Coulter
REGISTER OF DEEDS

For corners in

CHARLEVOIX
(County)

Located In:

Corner Code #/

- | | | | | | |
|---------------------------------------|---|------------|---|-----------|-------------|
| 1. Public Land Survey | T | <u>33N</u> | R | <u>4W</u> | <u>M-13</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling
in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, ARTHUR R. RANGER, in a field survey on SEPT. 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-13 GLO - Set post on bank of pond - Pine 16" N2°W 38 lks; Pine 16" S51°E 50 lks; E.K. Robinson, County Surveyor found corner in a survey dated 1881 - Witness: Pine 16" N2°W 38 lks; Pine 16" S51°E 50 lks; Previously recorded by Carl I. Robinson, Otsego County Surveyor in a survey dated 1987; (Co. survey Rec. L.4, P.482) Pine 16" S51°E 50 lks; Pine 16" N2°W 38 lks; Found a 1" iron pipe & concrete monument & pine stump reference, used concrete monument because it fit pine stump reference.

*See reverse side for remarks by Carl I. Robinson.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13 Found concrete monument and 1" iron pipe and Robinson witnesses previously recorded; Held concrete monument. (Found old pine stump witness).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13 Found concrete monument & iron pipe
Witness:

- 20" W. Pine N40°W 6.33'
- Old Pine stump N6°E 25.4'
- 8" Poplar N41°E 12.61'
- 10" W. Cherry S28°E 24.37'
- Ed. of lake West 11.50'
- 9" Maple S80°E 8.14'

Charlevoix Co. Surveyor
APPROVED
Signature Mary C. Fennell
Date: 10-3-93



AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Arthur R. Ranger

Date 01/03/96

Surveyor's Michigan License No. 31601

A. continued

M-13 (Co. survey Rec. L.4, Pg. 482) Pine 16" S51°E 50 lks; Pine 16" N2°W 38 lks.

M-13 Found 1" Iron pipe, concrete monument and pine stump reference. Used concrete monument because it fit pine stump reference.

M-13 Concrete monument: 6" Aspen N35°E 12.85'; 16" W. Pine N72°E 31.95';
8" Twin Cherry S25°E 24.78'; 16" W. Pine N35°W 6.89'

SURVEY &
REMONUMENTATION

DEC 16 1996

COMMISSION

15/96