

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. PA 1970

For Corners In: _____ Located In _____ Corner Code # _____
 Charlevoix _____
 (County)

1. Public Land Survey	T	33N	R	4W	I-10
	T	_____	R	_____	_____
2. Property Controlling in Section	S	T	R	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	T	R	_____	_____
	S	_____	T	_____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on August, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-10 G.L.O. Ch. W. Cathcart D.S. 1841
 Set quarter section post
 Wit: Beech 8 N45°W 3 Links
 Elm 4 N67°E 15 Links

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

I-10 Re-established the east quarter corner of section 27 on line between I-9 and I-11 on a good fence line going East and on an old mostly down fence line going west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10 Standard DNR monument
 Wit: 26" Maple N43°E 40.28'
 26" Maple S34°E 30.76'
 16" Maple S49°W 44.47'
 14" Maple N38°W 88.76'

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by: Carl T Kiiskila
 Surveyor's Michigan License No.: 33981

Date: 11-8-00