

FEB 22 2001

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

00 DEC 21 PM 2:05

SECTION
CHANDLER TOWNSHIP

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Charles W. Justice
REGISTER OF DEEDS

CHARLEVOIX (County) Located in: Corner Code #

1. Public Land Survey T 33N R 4W A-9 ✓
T 33N R 5W M-9
T R
T R

2. Property Controlling in Section S T R
S T R
S T R

3. Miscellaneous Property in Sec. S T R
S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, JAMES E. EVANS, in a field survey NOV 10, 2000 do hereby state that requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	6			4		3		2		1		
3													
4	7	8			9		10		11		12		
5													
6	18	17			16		15		14		13		
7													
8	19	20			21		22		23		24		
9													
10	30	29			28		27		26		25		
11													
12	31	32			33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 A-9 SECTION CORNER COMMON TO SECTIONS 19 & 30 T33N -R4W AND SECTIONS 24 & 25 T33N-R5W
 GLO: SET POST E. A. Robinson June 2, 1908 Carl Roser PS #12028 LCRC 1-12-1982
 Sugar 12" S19°W 23 lks (15.18') Found cedar stake Found well point. Did not accept Schaaf
 Sugar 10" N55°E 37 lks (24.42') Elm 6" N58 1/2°E 60 lks. (39.6') monument. Added cedar guard post
 May 23, 1840 Elm 7" S69°W 45.5 lks (30.03') Schaaf monument N05°E 12.65' (4)
 By: John Mullett D. S. Charlevoix Abstract June 9, 1976 Set wellpoint SP A-8 and A-10
 6" Maple West 16.26' (1)
 8" Maple N75°E 22.70' (2)
 3" Maple S48°E 17.70' (3)
 14" Maple N70°E 22.70' (2)
 4" Maple S50°E 17.75' (3)
 8" Maple S82°W 16.30' (1)
 Old N-S ROW fence East 22' ±

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner
 A-9 SECTION CORNER COMMON TO SECTIONS 19 & 30 T33N -R4W AND SECTIONS 24 & 25 T33N-R5W

FOUND WELL POINT IN CENTER LINE OF ABANDONED TWO TRACK ROAD.

Distance to A-8 = 2618.47' (GLO =2640.0' DNR = 2617.30' E. A. Robinson = 2650.56' Char. Abstract = 2617.82')

C. Description of monument for corner and accessories established to perpetuate location the position of the corner:
 A-9 SECTION CORNER COMMON TO SECTIONS 19 & 30 T33N -R4W AND SECTIONS 24 & 25 T33N-R5W

FOUND WELL POINT AND REPLACED WITH CHARLEVOIX COUNTY MONUMENT.

- 10" Maple S 81° E 16.32' Set nail & cap #22431 in old blaze mark in East side (1)
- 16" Maple N 75° E 22.37' Set nail & cap #22431 in old blaze mark in SW side. (N & S wire in tree) (2)
- 6" Maple S 53° E 17.86' Set nail & cap #22431 in old blaze mark in SW side (3)
- Found 2" pipe N 06° E 12.51' Old Schaaf monument (4)
- 8" Ironwood N 38° W 26.81' Set nail & cap #22341 in South side

And is accepted as the best available evidence of the position of the original corner.

Signed by *James E. Evans*
Surveyor's Michigan License No 22431

Date 12-21-00

Charlevoix Co. Surveyor
APPROVED
Signature *Mary C. Feinelt*
Date: 12-21-00

