

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: \_\_\_\_\_ Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 Charlevoix \_\_\_\_\_  
 (County)

1. Public Land Survey		T	33N	R	4W	B-2
		T		R		
2. Property Controlling in Section	S 6	T	33N	R	4W	2
	S	T		R		
3. Miscellaneous Property in Section	S	T		R		
	S	T		R		

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Carl T. Kiiskila, in a field survey on December 1, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-2 This corner position was not established during the original government survey.

2-John E. Ferguson June 8, 1982 L.L.S. #24595 set a 1/2" rod for the corner while doing a survey in the area.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

B-2 Established the center of section 6 at intersection of North-South and East-West quarter lines.

2- Found a 1/2" rod as set by John E. Ferguson.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-2 Set 5/8" X 32" iron with P.S. cap #33981  
 Wit: 12" Maple S06°W 10.44'  
 12" Basswood N50°E 27.81'  
 14" Basswood N13°E 21.20'  
 10" Basswood S75°E 32.37'  
 Blue Carsonite Post North 1'±

2- Added P.S. cap #33981 to found 1/2" rod  
 Wit: 18" R. Pine S70°W 111.90'  
 14" J. Pine N46°W 101.65'  
 18" R. Pine S11°W 106.16'  
 Centerline of road intersection N85°W 15'

Signed by: Carl T. Kiiskila  
 Surveyor's Michigan License No.: 33981

Date: 12-2-04

