

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Charlevoix (County)	Located In	Corner Code #
1. Public Land Survey	T <u>33N</u> R <u>4W</u>	<u>B-3</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No: _____	Recorded Plat: _____	
5. Private Claims: _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3	●												
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl T. Kiiskila, in a field survey on May 5, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-3 G.L.O C.W. Cathcart 1841 Set quarter section post
 Wit: Lynn 8" N20°W 30 Links
 Lynn 4" South 2 Links

County Surveyor E.A. Robinson book 32-A page 145 set ¼ post by proportionate measurement type of monument and witnesses not given.

1930 Marcus Schaaf R.L.S. #1304 found an iron 34.65 chains (2286.9') from west and 11.9' north of line. He set a wood stake online between A-3 and C-3 at proportionate measurement. No witnesses were given.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

B-3 Reestablished the South quarter corner of section 6 online between found corners A-3 and C-3 prorated to U.S. run out. No evidence of M. Schaaf or E.A. Robinson's corners was found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-3 Set 1" X 48" pipe with standard Department of Natural Resources aluminum cap.
 Wit: 14" Beech N15°E 18.59'
 28" Basswood N75°E 30.45'
 5" Maple S25°E 10.12'
 7" Maple S86°W 27.92'
 Blue Carsonite Post North 1±



Signed by: Carl T Kiiskila
 Surveyor's Michigan License No.: 33981

Date: 12-2-04