

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 33 N. R. 5 W.	I-9, G-9, E-10
2. PROPERTY CONTROLLING IN SECTION <u>27</u>	T. 33 N. R. 5 W.	1
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. R. _____ E. S. R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 6, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-9 Reestab. NE cor. Sec. 27 by double proportion to G.L.O.; 1 mile N, 1 mile S, 2 miles E, & 1 mile W. Cor. is on random line E & S. Random line W is 4'± north.
- 1 Etab. W 1/8 cor. on N line of Sec. 27 per std. B.L.M. instructions.
- G-9 Fd. 1" sq. iron per E.A. Robinson Jan. 2, 1908, E.A.R. had Govt cor. here. See "Melrose" book in Jury Room, Pg. 53.
- E-10 Reestab. 1/4 cor. to Sec's. 28 & 29 at prorated distance to E.A. Robinson Bet. fd. NE & SE cor's. of Sec. 29 and 33' East of old Ced. Cor. post. Cor. is in line with ctr. of gravel rd. to E & N. Robinson had original Govt cor. here; see Robinson's notes at Ct. Hse., "Melrose", Pgs. 62, 68 & 75, 1908 & 1909.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	I-9	G-9	E-10
Set DNR mon & ced. post		Fd. 1" sq. ir. buried & raised w/1 1/4" x 2' pipe & set ced. post w/loc. tag	Drove 5/8" x 36' rerod w/RLS cap (buried 0.4')
6" Maple	S65°W 7.0	8" Maple N40°E 62.1	SE cor. of metal garage S30°W 68.8
3" Maple	S15°E 40.4	12" Scotch pine S30°W 18.4	NW cor. of log garage S63°W 57.7
7" Maple	N85°E 67.2	Ctr. line U.S. 131 W 50.2	8" Maple S15°E 38.6
	1	Ctr. line R.R. track E 177'±	Set loc. tag on old ced. post West 33'
Set 5/8" rerod w/RLS cap & ced. post			
7" Tamrack	N50°E 13.4		
8" Tamrack	S85°W 18.3		
7" Tamrack	S20°E 19.0		
E-W Random	North 0.9'		


SIGNED BY Carl F. Roser 01-12-82 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

MELROSE TOWNSHIP
 CHARLEVOIX COUNTY