

SURVEY & RE-MONUMENTATION

OCT 18 1996

COMMISSION

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX

96 SEP 19 PM 4: 14

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Charles J. Brand
REGISTER OF DEEDS

For corners in

Charlevoix
(County)

Located In:

Corner Code //

- Public Land Survey T 33N R 5W **A-9**
- T 33N R 6W M-9
- T R
- T R
- Property Controlling S T R
- in Section S T R
- Miscellaneous S T R
- Property in Sec. S T R

Register of Deeds Stamp & File Number

- Lot No. _____, Recorded Plat _____
- Private Claims _____

Terry E. Brand in a field survey on **June 18, 1996**, 19
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

A-9 corner common to Section 19 & 30, T33N-R5W & M-9 Section 24 & 25, T33N-R6W

- 840. Twp Lines by J. Mullett. Set cor. post. Sugar 10" S17°W 29lks. (19.14'), Beech 6" N43°E 22lks. (14.52')
- 841. Sub. of Twp., by C.W. Cathcart. Fd. cor. post. Beech 6" S45°E 20lks. (13.2'), Sugar 8" N65°E 54lks. (35.64')
- 877. Co. Surveyor E.K. Robinson (Co. Surveyor bk. pg. 335), Fd. cor. post. Beech 6" N43°E 22lks. (14.52'), & New B.T. Sugar 10" S55°W 64lks. (42.24')
- 908. Co. Surveyor E.A. Robinson, Co. Surveyor bk. pg. 348 & Shows cor. on Minutes of Survey Hwy. Survey, Elm 6" N58½°E 60lks. (39.6'), Elm 7" S69°W 45½lks. (30.03')
- 962. R. Kent cor. Reg. Lib.1 Pg. 123, Fd. cor. 1½" Pipe 4" above ground. Elm 19" S34°W 35.24', Cherry 16" S75°W 41.04', Elm 7" N43°E 40.22', Maple 8" S13°W 14.16'
- 969. Co. Surveyor Mary Feindt. Shows corner on Certificate of Survey, No accessories.
- 976. Granger Engineering Inc., Fd. 1" Iron Pipe on Certificate of Survey. Liber 238 Page 800. MDSH tag Elm 20" S30°W 35.22', tag tw. Maple 12" S15°W 14.20', tag Maple 12" N45°E 41.80'
- 978. John E. Ferguson RLS #24595, LCRC. Liber 002, Pg. 83, Fd. 1½" Pipe. Elm 19" S34°W 35.24', Cherry 16" S75°W 41.04', Elm 7" N43°E 40.22', Maple 8" S13°W 14.16'
- 987. Surveyor Unknown, Fd. 1" Pipe on Easement Drawing. Liber 299 Page 657. Elm 20" S30°W 35.33', tw. Maple 12" S15°W 14.20', Maple 12" N45°E 41.80'

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-9 corner common to Section 19 & 30, T33N-R5W & M-9 Section 24 & 25, T33N-R6W

- Fd. 1½" x 5' pipe at "T" intersection of fences
- Fd. nail & tag(MSHD) in 18" Ironwood(previously called Elm), S34°W, 35.22'
- Fd. 19" Cherry Stump, S71°W, 41.1' Fd. nail in 10" Tw. Maple, S06°W, 14.17'

Charlevoix Co. Surveyor
APPROVED
Signature: *Mary C. Feindt*
Date: *8-29-96*

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9 corner common to Section 19 & 30, T33N-R5W & M-9 Section 24 & 25, T33N-R6W

- Fd. 1½" x 5' pipe at "T" intersection of fences. Replaced with 3" cast iron Charlevoix County Monument.
- Fd. nail & tag(MSHD) in 18" Ironwood(previously called Elm), S34°W, 35.22'
- Fd. 19" Cherry Stump, S71°W, 41.1' Fd. nail in 10" Tw. Maple, S06°W, 14.17'
- Set nail & tag in 4" Tri. Ironwood clump, N53°W, 28.21' Set nail 7 tag in 14" Maple, N53°W, 28.21'

Found corner is accepted as a careful and faithful **perpetuation** of the position of the original corner.

Signed by *Terry E Brand*

Date *8-29-96*

Surveyor's Michigan License No. 33969

LIBER 003 PAGE 17