

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Charlevoix (County)	Located In	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>11</u> T <u>33N</u> R <u>5W</u>	<u>2</u>
	S <u>11</u> T <u>33N</u> R <u>5W</u>	<u>16</u>
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Carl T. Kiiskila, in a field survey on August, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3										●			
4	7		8		9		10		11		12		
5										●			
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

2- This corner position was not established during the original government survey.

16- Liber 2, Page 124 Carl F. Roser R.L.S. #12028 set a 5/8" X 32" rerod while doing a survey in section 14 November 1981.

Wits. 8" Cherry                    N55°E    49.53'  
     P. Pole        S60°E    109.00'  
     1/2" Pipe        N50°E    16.00'  
     Center line of E-W Rd. South    5'

**B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:**

2- Established the Northwest corner of the Northeast quarter of the Northeast quarter of section 11 per B.L.M. instructions for the subdivision of a section.

16- Found 1/2" bar as set by C.F. Roser.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

2- Set 5/8" X 32" rerod with P.S. cap #33981  
 Wit: 6" Ironwood                    N88°W    10.88'  
     12" Beech clump                    N30°E    36.78'  
     10" Maple                            N67°E    30.43'  
     12" Maple                            S43°E    10.22'  
     Carsonite Post                    North    1'±

16- Found 1/2" bar added P.S. cap #33981  
 Wit: 5" White Pine                    S15°E    38.58'  
     P. Pole                                S81°W    113.32'  
     4" Cherry                            N56°W    38.42'  
     5" Cherry                            N01°W    34.08'  
     Carsonite Post                    North    33'±  
     Center line of Eastwood Rd. South 5'

Signed by: Carl T. Kiiskila  
 Surveyor's Michigan License No.: 33981

Date: 12-23-02

