

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Charlevoix (County)	Located In	Corner Code #
1. Public Land Survey	T 33N R 5W	I-1
	T 33N R 5W	I-2
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No: _____	Recorded Plat: _____	
5. Private Claims: _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Carl T. Kiiskila, in a field survey on July 23, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---|---|
| I-1 G.L.O. John Mullet 1840 set post for corner 2 and 3.
Wit: Cedar 6 N40°E 12 links
Cedar 8 S50°W 15 links | I-2 G.L.O. C. W. Cathcart August 1841 set quarter section post. Wit: Cedar 8 N20°W 7 links
Cedar 8 N30°E 14 links |
| 1974 James Green found cedar post replaced with 3/4" X 18" iron pipe Wit: 11" Spruce S15°W 50.00'
13" Tamarack N39°E 61.55'
6" Spruce N42°W 62.85'
3/4" iron pipe West 9.45' | Book 32-A Charlevoix County Survey Records E.K. Robinson 1894 shows corner position with distance East. No witnesses or type of monument given. |
| June 1997, Tom Swenor P.S.#37282 Found 5/8" pipe, replaced with 1/2" rerod W/P.S. cap # 37282 measures 9.87' west to 1" pipe. | |

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

- | | |
|---|---|
| I-1 Found 1/2" iron rod W/P.S. cap #37282 | I-2 Found 1" iron bar that fits work done by E.K. Robinson in 1889. He did not make a record of setting this corner however the 1" bar fits his recorded distances reasonably well. |
|---|---|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| I-1 Found 1/2" capped iron rod.
Wit: 5" Cedar S39°E 38.46'
20" W. Pine S04°W 23.75'
14" Tamarack N19°W 27.51'
16" Tamarack N43°E 61.91'
1/2" Found pipe N80°W 9.84' | I-2 Found 1" iron bar
Wit: 5" Maple North 15.25'
6" Maple N80°E 40.52'
7" Ironwood S39°W 6.13'
14" Maple N85°W 28.89'
Blue Carsonite Post North 1'± |
|--|--|

Signed by:

Carl T. Kiiskila

Date:

12-23-02

Surveyor's Michigan License No.:

33981

