

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
 Charlevoix _____
 (County)

Located In						Corner Code #
1. Public Land Survey	T _____	R _____				
	T _____	R _____				
2. Property Controlling in Section	S <u>2</u>	T <u>33N</u>	R <u>5W</u>			<u>12</u>
	S <u>2</u>	T <u>33N</u>	R <u>5W</u>			<u>13</u>
3. Miscellaneous Property in Section	S _____	T _____	R _____			
	S _____	T _____	R _____			

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on August, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3			2		1	
3										•	•		
4	7		8		9		10			11		12	
5													
6	18		17		16		15			14		13	
7													
8	19		20		21		22			23		24	
9													
10	30		29		28		27			26		25	
11													
12	31		32		33		34			35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

12- This corner position was not established during the original government survey.

13- This corner position was not established during the original government survey.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

12- Established the Northwest corner of the Southwest quarter of the Southeast quarter of section 2 as per B.L.M. instruction for the subdivision a section.

13- Established the Northeast corner of the Southwest quarter of the Southeast quarter of section 2 as per B.L.M. instructions for the subdivision of a section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

12- Set 5/8" X 32" reroed with P.S. cap #33981
 Wit: 8" Hemlock S49°W 27.65'
 7" Cedar N33°W 16.14'
 Power Pole N30°E 100.80'
 6" Balsam S77°E 90.78'
 Center of N-S Power line East 40'±
 Blue Carsonite Post North 1'±

13- Set 5/8" X 32" reroed with P.S. cap #33981
 Wit: 7" Yellow Birch N81°W 21.58'
 10" Cedar N01°W 17.10'
 11" Maple S78°E 8.25'
 11" Balsam N11°W 35.49'
 Blue Carsonite Post North 1'±

Signed by: Carl T. Kiiskila
 Surveyor's Michigan License No.: 33981

Date: 12-23-02

