

No 6.

$\frac{1}{8}$  Corner South of center of  
Sec 21 T33N R6W  
established by C.M.G. 1978.  
on a true line between center  
of section and  $\frac{1}{4}$  Cor on South  
line of Section - equidistant from each.  
An old  $\frac{1}{8}$  post was lying alongside  
fence post 12' north.

6" elm on north side Curvain road

N 77 W 52.7'

8" poplar N 26 W 24.9'

10" " N 55 E 21.0'

Fence runs south + east from  
this point.

Standard Monument

No 7.

In cedar Swamp -  $S \frac{1}{4}$  Cn Sec 21

as re-set by E.A. Robinson in 1888

6" Spruce N 40 E 29.45'

6" " S S W 18.40

8" Balsam S S W 23.80

Std. Mon

No 8.

Iron pipe 2640' west of  $S \frac{1}{4}$  Corner  
of Section 21 T33N R6W.  
Sec. p 129.

No 9.

Meander line on old shore line  
' from an established corner of  
Section 21 2.8' above present water  
level and 1.5' above H.W.M.

Iron meander stake S E

5" Cedar N 30° E 21.8'

5" Norway N 34° W 44.5'

No 10.

A 4" iron pipe filled with concrete  
' from shore line to monument