

**SURVEY &
REMONUMENTATION**

JAN 26 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

97 DEC 16 AM 10:15

Charlotte M. Barber
REGISTER OF DEEDS

For corners in

<u>CHARLEVOIX</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T 33NR 6W</u>	<u>C-13</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ARTHUR R. RANGER, in a field survey on SEPT. 15, 1997
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-13 corner common to Sec.'s 31 & 32, T.33N., R.6W.
1840-John Hodgson set a Post corner to Sec.s 31 & 32 and witnessed: Hemlock 10" N17°W 11lks.; Hemlock 18" N47°E 17lks.
1878-E.K. Robinson used the corner in a survey in Sec. 31, T.33N., R.6W.
1881-E.K. Robinson used the corner in a survey in Sec. 32, T.33N., R.6W.
1885-E.K. Robinson used the corner in a survey along the North line of Sec. 5, T.32N., R.6W.
1888-E.K. Robinson used the corner in a survey in Sec. 31, T.33N., R.6W.
1973-Mary Feindt set a t-iron using single proration, based on Robinson work along the Town line.
1981-Mary Feindt found the T-iron and witnessed: 5" pine N20°W 12.80'; 5" Pop. N65°E 14.50'; Fe post N60°E 49.00'
1995-John Ferguson found Mary Feindt t-iron--no witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13 corner common to Sec.'s 31 & 32, T.33N., R.6W.
1997-Arthur R. Ranger found the t-iron set by Mary Feindt and the witnesses of record; The distance to Porter Creek to the West Matched GLO. Also the distance to the East agreed with the Robinson meas. Reasonably well.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 corner common to Sec.'s 31 & 32, T.33N., R.6W.
(Set a Charlevoix County Monument)
9" W. Pine N55°W 23.08'
13" W. Pine N24°W 12.61'
13" Pop. S06°W 42.53'
8" Cedar S30°W 37.37'

Charlevoix Co. Surveyor
APPROVED
Signature Mary C. Feindt
Date: 12-0-11-97

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF POSITION OF THE ORIGINAL CORNER.

Signed by Arthur R. Ranger Date 12/06/97
Surveyor's Michigan License No. 31601



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983
REVISED OCT., 1995