

SURVEY & REMONUMENTATION

JAN 26 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

97 DEC 16 AM 10:13

Charlotte M. Probert
REGISTER OF DEEDS

For corners in

<u>CHARLEVOIX</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>33NR 6W</u>	<u>E-13</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling In Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ARTHUR R. RANFER, in a field survey on SEPT. 15, 1997
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
E-13 Corner common to Sec.'s 32 & 33 of T.33N., R.6W.
1840-John Hodgson set the post to Sec.'s 32 & 33 and witnessed: Beech 7" N54°E 21lks;
Beech 6" N76°W 13 lks.
1881-E.K. Robinson used the corner in his survey of Sec. 32, T.33N., R.6W.
1882-E.K. Robinson used the corner in a survey along the North line of Sec. 4, T.32N., R.6W.
1973-Charlevoix Abstract found iron and used in a large survey along the Townline.
1974-Mary Feindt found a 3/4" iron pipe and rec. In L.C.R.C. (L.02, Pg. 15) and witnessed: 6" Box Elder North 21.80';
10" Maple S10°W 24.20'; 12" Maple S80°W 54.20'.
1977-Larry Feindt found a 3/4" iron in a survey in Sec. 4, T.32N., R.6W., and witnessed: witnesses same as above.
1995-Sherm Chamberlain used the 3/4" iron in the survey he did in Sec. 32, T.33N., R.6W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E-13 Corner common to Sec.'s 32 & 33 of T.33N., R.6W.
1997- Arthur R. Ranger found the 3/4" iron and the witnesses of record. The corner fits the old E.K. Robinson measurements Quite well.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-13 Corner common to Sec.'s 32 & 33 of T.33N., R.6W.
(Set a Charlevoix County monument)
10" Ash N04°E 22.17'
14" Maple S07°W 24.37'
9" Tw. Maple S20°W 32.09'
13" Maple N54°W 51.20'

Charlevoix Co. Surveyor
APPROVED
Signature Mary C. Feindt
Date: 12-11-97

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Arthur R. Ranger Date 12/05/97
Surveyor's Michigan License No. 31601



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995