

**SURVEY & REMONUMENTATION**

**JAN 26 1998**

STATE OF MICHIGAN  
COUNTY OF CHARLEVOIX  
RECEIVED FOR RECORD

97 DEC 16 AM 10:12

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

*Charles M. Prater*  
REGISTER OF DEEDS

For corners in

<u>CHARLEVOIX</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>33NR</u> <u>6W</u>	<u>F-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, ARTHUR R. RANGER, in a field survey on SEPT. 15, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:  
F-13 South 1/4 corner Sec. 33, T.33N., R.6W.  
 1840-John Hodgson set a 1/4 Sec. Post and witnessed: Hemlock 24" N72°E 29lks; Elm 24" N53°W 37lks.  
 1880- E.K. Robinson refers to the gov't stake in his survey along the North line of Sec. 4, T.32N., R.6W.  
 1963-Mary Feindt shows the corner on her Plat of "Lake View Heights"  
 1973-Mary Feindt refers to the corner in a survey in Sec. 33, T.33N., R.6W.  
 1977-Larry Feindt shows he found a 3/4" iron pipe in his survey in Sec. 4, T.32N., R.6W., and witnessed: 8" Pop. N40°E 60.4'; 6" Pop. N28W 44.0'; 8" Pop. S50°W 65.2'; 10" Pop. S25°E 45.7'.  
 1978-Charlevoix Abstract shows the corner on a survey in Sec. 33, T.33N., R.6W.  
 1989-John Ferguson found a 3/4" iron pipe in a survey in Sec. 33, T.33N., R.6W., and witnessed: Same witnesses as above.  
 1992-Mary Feindt found a 1" iron pipe and witnessed: 7" Map. S15°E 34.02'; 15" Pop. S45°W 65.13'; 7"Map. N30°W 34.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
F-13 South 1/4 corner Sec. 33, T.33N., R.6W.  
 1997- Arthur R. Ranger found the 3/4" iron pipe and the witnesses of record. The corner fits old Robinson measurements  
 Quite well.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
F-13 South 1/4 corner Sec. 33, T.33N., R.6W.  
 (Set a Charlevoix County marker in a monument box)  
 6" Ash N52°E 68.00'  
 7" Maple S05°E 34.85'  
 9" Maple S24°W 47.21'  
 9" Ash N39°W 59.35'

Charlevoix Co. Surveyor  
**APPROVED**  
 Signature Mary C. Feindt  
 Date: 12-11-97

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Arthur R. Ranger  
 Surveyor's Michigan License No. 31601

Date: 12/05/97



APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983  
 REVISED OCT., 1989