

SURVEY & REMONUMENTATION

JAN 26 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

97 DEC 16 AM 10:11

Charles M. Becken
REGISTER OF DEEDS

For corners in

CHARLEVOIX
(County)

Located In:

Corner Code #

1. Public Land Survey

T 33NR 6W

G-13

2. Property Controlling in Section

S _____

T _____ R _____

S _____

T _____ R _____

3. Miscellaneous Property in Sec.

S _____

T _____ R _____

S _____

T _____ R _____

T _____ R _____

T _____ R _____

T _____ R _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ARTHUR R. RANGER, in a field survey on SEPT. 15, 1997
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
G-13 Corner common to Sec.s 33 & 34 of T.33N., R.6W.
1840-John Hodgson mentioned that a Sugar 40" in dia. for the corner--no witnesses.
1877-E.A. Robison refers to the corner in his survey notes of Sec. 3, T.32N., R.6W.
1973-Corner used in a survey by Charlevoix Abstract in Sec. 33, T.33N., R.6W.
1974-Corner used in a survey by Charlevoix Abstract in Sec. 34, T.33N., R.6W.
1989-John Ferguson found a 2" iron in mon. Box, and used in his survey in Sec. 33, T.33N., R.6W.--witnesses:
P.P. N4°W 35.73'; P.P. S20°W 65.75'; 30" Bass. S37°E 50.0'; S.W. cor. conc. Drive N48°E 53.43'
1989-Mike Trowbridge survey in Sec. 3, T.32N., R.6W.
199 -Sherm Chamberlain sketch showing the relationship of the corner to the N.W. corner of Sec. 3, T.32N., R.6W.
1995, John Korr show the corner in his survey of Harborage Park

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
G-13 Corner common to Sec.s 33 & 34 of T.33N., R.6W.
1997-Arthur R. Ranger found the 2" iron in mon. Box and witnesses of record. The corner found fits old survys in the area and old Robinson and GLO measurements.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-13 Corner common to Sec.s 33 & 34 of T.33N., R.6W.
(Found 2" iron in mon. Box)
P.P. N2°W 35.82'
P.P. N72°E 99.80'
P.P. S72°E 116.3'
P.P. S72°W 85.66'

Charlevoix Co. Surveyor
APPROVED
Signature Mary C. Feindel
Date: 12-11-97

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Arthur R. Ranger
Surveyor's Michigan License No. 31601

Date 12/05/97



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1993

002 DATE 150