

SURVEY & REMONUMENTATION

JAN 26 1998

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

97 DEC 16 AM 10:10

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

CHARLEVOIX
(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|-------|------------------|-------------|
| 1. Public Land Survey | | <u>T 33NR 6W</u> | <u>H-13</u> |
| | | T ___ R ___ | _____ |
| | | T ___ R ___ | _____ |
| | | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ | T ___ R ___ | _____ |
| | S ___ | T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ | T ___ R ___ | _____ |
| | S ___ | T ___ R ___ | _____ |

Charlotte M. Probert
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, ARTHUR R. RANGER, in a field survey on SEPT. 15, 1997
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
H-13 1/4 corner for Sec. 34, T.33N., R.6W.
1839-John Hodgson set 1/4 Sec. Post and witnessed: Elm 24" N75°W 27lks
1901-E.A. Robinson found the post and used in a survey in Sec. 34
1980-Thomas sutherland (L.C.R.C.) —Eroneous!

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
H-13 1/4 corner for Sec. 34, T.33N., R.6W.
1997-Arthur R. Ranger found no evidence of the corner or witnesses; The corner was reestablished using the old 1901 Notes. The old meander corners, and 1/8th corners perpetuated by the Robinson's and Mary Feindt were used To determine the East & West position of the corner. Also E.S. Johnson's Addition to Boyne was helpful; The Corner was set on line between H-1 and I-1 of T.32N., R.6W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
H-13 1/4 corner for Sec. 34, T.33N., R.6W.
(Set a Charlevoix County Monument in a monument box)
6" Elm North 35.04'
18" Walnut S37°E 41.98'
P.P. S58°E 63.54'
N.E. cor. Hse. S28°W 90.82'

Charlevoix Co. Surveyor
APPROVED
Signature Mary C. Feindt
Date: 12/11/97

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Arthur R. Ranger
Surveyor's Michigan License No. 31601

Date 12/05/97



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995